

ADDENDUM NO. 1

TO: ALL PLAN HOLDERS
DATE: AUGUST 28, 2017
FROM: CITY OF LONGVIEW
TRANSIT BUILDING ROOF RENOVATIONS

The plans, specifications, and contract documents are modified as described below. All bidders shall acknowledge receipt of this and all other addenda on page P-2 of the proposal. This addendum becomes a part of the contract documents. All provisions of the original plans, specifications, and contract documents shall remain in full force and effect, except as modified by this addendum.

1. **Division 07 Theromal Plastic Poloyolefin (TPO) page 075423-3; Part 2-Products 2.1.A- Add 2.1.A-5. Mule-Hide Products Co., Inc.**
This product was reviewed and approved for use on this project.
2. **Materials used to level ponding areas of roof shall be acceptable to Warrantor of roof and shall not load the existing roof structure beyond its safe capacity.**
3. **As directed by Owner, remove and dispose of 40 lineal feet of existing gutter and replace with matching which appears to be 5" Type K, galvanized and field painted. Field verify size and profile. Paint System and color to match existing.**

ADDENDUM NO. 1 ISSUED BY:



**Douglas J. Camp A.I.A
Johnson & Pace Incorporated**